


02 ENLARGED SECOND FLOOR PLAN
A102 1/4" = 1'-0"

SECOND FLOOR - FLOOR SHEATHING:
ALL PLYWOOD PANELS TO BE ORIENTED PERPENDICULAR TO THE SPAN OF THE JOISTS, WITH END JOISTS ALTERNATING. ALL PLYWOOD PANEL ENDS SHOULD BE BLOCKED. FLOOR JOIST MANUFACTURER TO ACCOMMODATE DEAD LOAD OF 3/8" TILE FLOORING IN RESTROOMS. PER TILE ASSOCIATION GUIDELINES, AREAS THAT HAVE TILES APPLIED TO HAVE A DEFLECTION NOT GREATER THAN 1/360 OF THE SPAN WHEN MEASURED UNDER A 300 LB CONCENTRATED LOAD.

ALIGNMENT AND REPLICATION OF EXISTING CONSTRUCTION:
FINISHES AND GEOMETRY OF NEW CONSTRUCTION TO MATCH EXISTING. THIS INCLUDES PLACEMENT OF EXTERIOR WALLS, EXTERIOR SIDING, ALL ROOF AND OVERHANG COMPONENTS. DIMENSIONS SHOWN ON THESE DRAWINGS ARE BASED ON ORIGINAL 1982 DRAWINGS AND NEED TO BE FIELD VERIFIED BY CONTRACTOR PRIOR TO FINAL LAYOUT, FABRICATION, AND/OR CONSTRUCTION. PROPER VERIFICATION MAY REQUIRE EXPLORATORY IN CONCEALED AREAS.

- GENERAL NOTES**
- DO NOT SCALE DRAWINGS.
 - CONTRACTOR TO VISIT SITE AND FAMILIARIZE HIMSELF WITH CONDITIONS PRIOR TO SUBMITTING BID FOR WORK.
 - ANY DISCREPANCIES, CONFLICTS, AND OMISSIONS ARE TO BE REPORTED TO DESIGN TEAM IMMEDIATELY FOR RESOLUTION. DESIGN TEAM INCLUDES CONTRACTOR, ARCHITECT, DESIGN-BUILD ENGINEERS, AND CHURCH BUILDING COMMITTEE.
 - ALL DIMENSIONS TAKEN FROM FACE OF STUD, CONCRETE, MASONRY, COLUMN CENTERLINE, OR FACE OF EXISTING FINISHES UNLESS NOTED OTHERWISE. DIMENSIONS NOTED AS CLEAR (CLR) INDICATE SPANS BETWEEN FINISH SURFACES.
 - DRAWINGS FROM ALL DISCIPLINES TO BE USED TO LOCATE ALL CONSTRUCTION ELEMENTS. COORDINATE ALL WORK WITH OTHER DISCIPLINES.
 - ALL WALLS TO EXTEND TIGHT TO STRUCTURE ABOVE UNLESS NOTED OTHERWISE. SEAL JOINT AT TOP AND BOTTOM OF WALLS WITH ACOUSTICAL SEALANT, TYPICAL.
 - SEE A101 FOR TYPICAL WALL TYPES. USE MOISTURE RESISTANT GYP. BO. IN WET OR HIGH MOISTURE LOCATIONS INCLUDING BATHROOMS, KITCHENS, LAUNDRY, AT SINKS, AND OTHER SIMILAR LOCATIONS UNLESS CEMENT BOARD IS CALLED FOR IN THE WALL-TYPE LEGEND.
 - WHERE WALLS ARE CALLED OUT TO RECEIVE SOUND ATTENUATING BATT, EXTEND BATTS FULL HEIGHT AND WIDTH OF THE WALL.
 - EXISTING BUILDING APPEARS AS GREY LINENWORK.
 - NEW CONSTRUCTION TO ALIGN WITH FACE OF ADJACENT SURFACE WHEN SHOWN. MATERIALS, CONSTRUCTION AND FINISH TO MATCH EXISTING PER PLAN.
 - FOR ALL PERMANENTLY MOUNTED CABINETS, FIXTURES AND EQUIPMENT, PROVIDE FIRE TREATED BLOCKING AND ANY SUPPLEMENTAL FRAMING REQUIRED TO PROVIDE A SOLID, PERMANENT INSTALLATION.
 - ALL WALLS ARE TO BE TYPE [A] UNLESS OTHERWISE NOTED ON THE PLANS. SEE SHEET A101 FOR WALL TYPES.
 - INSTALL AUTOMATIC SPRINKLER SYSTEM THROUGHOUT NEW BUILDING. FIRE PROTECTION DESIGN/BUILDER IS RESPONSIBLE FOR CODE COMPLIANCE OF SYSTEM.

- PLAN KEY NOTES**
- SALVAGE EXISTING FOLDING PARTITION FROM NURSERY 127. INSTALL NEW SUPPORT HEADER TO CARRY APPROXIMATE 600# LOAD OF PARTITION. RELOCATE PARTITION AND REPLICATE TRACK-HEADER DETAIL EXACTLY IN NEW ROOM. PARTITION OPENING WIDTH TO MATCH EXISTING (REQUIRES FIELD VERIFICATION AND COORDINATION). FRIED WALLS REQUIRE BLOCKING TO SUPPORT HINGED CLOSET PANEL AND RESIST IMPACT DURING OPERATION. REFER TO 06/A602.
 - NOT USED.
 - REMOVE & SALVAGE EXISTING CASEWORK FOR REINSTALLATION. REPAIR AFFECTED AREA AS REQD. COORDINATE WITH OWNER. SEE NEXT NOTE.
 - REINSTALL SALVAGED CASEWORK (THIS LOCATION AND RETROFIT WITH NEW SINK. COORDINATE AND CONFIRM ALL DETAILS WITH OWNER BEFORE UNDERSLAB PLUMBING ROUGH-INS OCCUR.
 - NOT USED.
 - VERTICAL LIFT. AMCO "MOTIVATOR" VERTICAL WHEELCHAIR LIFT. SEE A501.
 - REMOVE & SALVAGE EXISTING CHILDS TOILET FIXTURE FROM ROOM 136. RE-INSTALL FIXTURE IN ROOM 156.
 - FLOOR & ROOF FRAMING PACKAGE DESIGN-BUILD BY OTHERS. SUBMIT SHOP DRAWINGS WITH REQUIRED CONNECTIONS FOR ARCHITECT REVIEW. REFER TO SPECS.
 - INFILL STAIRWELL. SEE 01/A310. SEE FINISH SCHEDULE FOR FINISHES.
 - NEW CASEWORK IS SUPPLIED AND INSTALLED BY OWNER. COORDINATE DIMENSIONS WITH OWNER PRIOR TO CONSTRUCTION TO CONFIRM PLUMBING ROUGH-INS, CUTOUTS, WALL BLOCKING, AND WING WALL PLACEMENT.
 - NOT USED.
 - RE-ROUTE EXISTING DUCTWORK/VENISERS AS REQUIRED TO WORK WITH NEW CONSTRUCTION.
 - ATTIC AREA ACCESS DOOR (DESIGN-BUILD BY CONTRACTOR. NOT PART OF DOOR PACKAGE). WOOD FRAMED ACCESS DOOR WITH KEYLOCK ENTRY AND (2) BUTT HINGES. 30" x 48" DOOR PANEL IS 3/4" PAINTED MDF BOARD. DOOR TO BE WEATHERSEALED AND INSULATED.
 - INSPECT AND REINFORCE EXISTING LOAD BEARING WALL AS REQUIRED FOR ENLARGED DOOR OPENING.
 - SEMI-RECESSED FIRE EXTINGUISHER CABINET. REFER TO SPECS.
 - 10 LB A-B-C FIRE EXTINGUISHER ON SURFACE MOUNTED HOOK.
 - REMOVE EXISTING CONSTRUCTION AS REQUIRED FOR NEW CLOSET DOOR IN STAIRWELL. PATCH WALL TO MATCH EXISTING ADJACENT MATERIALS AND FINISH.
 - PEDESTAL DOOR ACTUATOR WITH RAIN GUARD.
 - NON-RATED WALL TO CONCEAL PIPE OR DUCTWORK THAT PENETRATES FLOOR SUBSTRATE. HOLD DIMENSION TIGHT TO MINIMIZE FOOTPRINT.



02 SECOND FLOOR PLAN
A102 1/8" = 1'-0"

BROWNING DAY MULLINS DIERDORF ARCHITECTS

Browning Day Mullins Dierdorf Architects
Architecture
Landscape Architecture
Planning
626 North Illinois Street
Indianapolis, Indiana 46204
P: 317.633.6300
F: 317.634.5409
E: mfoerster@bdmd.com (Matt Foerster)

First Mennonite Church, Indianapolis
Owner, Project Location

4801 Knollton Road
Indianapolis, Indiana 46228
P: 317.251.1980
F: 317.251.1980
E: dalt@bdmarchitect.com (Dave Talbot)

Integrity Commercial Management
Construction Manager / Contractor

428 East Main Street
Brownsburg, Indiana 46112
P: 317.868.2370
F: 317.862.1947
E: info@stbcglobal.net (Dave Wagley)

Charlier Clark Linard PC
Structural Consultants

5242 Central Ave
Indianapolis, Indiana 46220
P: 317.448.8735
F: 317.255.5119
E: glinard@cdpc.com (Gary Linard)

RTM Consultants
Code Consultant

6640 Parkside Place, Suite J
Indianapolis, Indiana 46254
P: 317.393.7700
F: 317.399.8411
E: rnsank@rtmconsultants.com (Ed Rensink)

Roger Ward Engineering, Inc.
Civil Engineers

5400 N. College Ave, Suite 202
Indianapolis, Indiana 46220
P: 317.251.1738
F: 317.209.4036
E: mmapple@rwe-engineering.com (Matt Maple)

JW Sims & Associates
Mechanical, Electrical, and Plumbing Engineers

1545 Country Club Road
Indianapolis, Indiana 46234
P: 317.209.4036
F: 317.209.4036
E: jwsims@jwsims.com (Joseph Sims)



CERTIFICATION
CONSTRUCTION DOCUMENTS

FIRST MENNONITE CHURCH ADDITION
4601 Knollton Road
Indianapolis, IN

Project No: 08015
Drawn By: MF, JM
Checked By: See Drawing
Issue Date: 10 MAR 2009
Revision # - Date of Issue:

SECOND FLOOR PLAN

A102